



Peatland Restoration Audit Report

Pulang Pisau, Central Kalimantan | Monitoring period: April-June 2026 | Record PP-PEAT-2026-001

RESTORATION AREA 250 ha Boundary-aligned area	WATER TABLE -28.1 cm Q2 mean, improving	CANAL BLOCKS 12 / 12 Operational structures
--	--	--

Executive finding

The reviewed evidence supports active rewetting and native vegetation recovery across the declared restoration block. Water-table observations show a progressive rise from an April mean of -38.9 cm to a June mean of -27.4 cm. The evidence package is internally consistent with the submitted boundary, monitoring locations, and restoration schedule.

Audit scope

Control	Procedure	Result
Project boundary	Compared GNSS polygon with survey composite	Consistent; 250.0 ha reported
Hydrology	Reviewed three water-level logger series	Improving water table; no missing periods
Canal blocking	Inspected register and geo-tagged structure points	12 structures operational
Vegetation	Reviewed 20 permanent sample plots	78.6% weighted survival rate
Chain of custody	Matched filenames, timestamps, and evidence identifiers	No material mismatch detected

Risk assessment

Risk	Rating	Basis	Mitigation
Fire recurrence	Medium	Dry-season exposure remains material	Maintain patrols and water-level alert threshold
Boundary leakage	Low	Boundary is separated from active cultivation	Quarterly perimeter inspection
Sensor interruption	Low	Battery remains above 87%	Replace batteries before September
Vegetation mortality	Medium	Two plots below 70% survival	Targeted enrichment planting



Hydrological monitoring

Field logger summary and restoration performance indicators

APRIL MEAN -38.9 cm Below ground surface	MAY MEAN -31.6 cm 7.3 cm improvement	JUNE MEAN -27.4 cm Target band achieved
--	--	---

Station	April mean	May mean	June mean	Q2 change	Quality
PP-WL-01	-36.5 cm	-30.6 cm	-26.5 cm	+10.0 cm	Valid
PP-WL-02	-40.3 cm	-34.5 cm	-30.7 cm	+9.6 cm	Valid
PP-WL-03	-35.2 cm	-29.8 cm	-25.7 cm	+9.5 cm	Valid

Interpretation

All three stations show directional improvement after canal-block maintenance. June readings remain within the project operational target of -40 cm or wetter. The dataset contains regular fortnightly observations, stable coordinates, and no quality flags requiring exclusion.

Evidence register

Evidence	Identifier	Review status
Water-level sensor CSV	PP-SENSOR-Q2-2026	Accepted
Restoration boundary GPS JSON	PP-GEO-2026-001	Accepted
Drone survey composite	PP-DRONE-BLOCK-A-2026	Accepted for demo
Vegetation survival report	PP-VEG-Q2-2026	Accepted
Auditor attestation	PP-ATT-2026-001	Accepted



Conclusion and recommendations

Independent evidence review summary

Conclusion

The submitted evidence supports the claim that restoration activities are underway across 250 hectares. The package demonstrates hydrological improvement, functioning canal blocks, monitored vegetation recovery, and a traceable spatial boundary. This demonstration audit assigns a Medium project risk because dry-season fire exposure and localized seedling mortality still require active management.

Required follow-up

Priority	Action	Due date	Owner
High	Enrichment planting in plots P-07 and P-14	31 Jul 2026	Field restoration lead
High	Confirm dry-season patrol roster	15 Jul 2026	Site manager
Medium	Replace logger batteries below 90%	31 Aug 2026	Monitoring officer
Medium	Repeat drone survey after peak dry season	15 Oct 2026	GIS specialist

OVERALL RISK	MEDIUM	CONFIDENCE	82%
--------------	--------	------------	-----

Prepared for CarbonProof AI hackathon demonstration. This report is synthetic demo evidence and is not a legal carbon certification, assurance opinion, or regulatory filing.